

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64


No:EE/YNK-D/E-PMT/04/2022-23 Dated: 12-05-2022

APPROVED TENDER SCHEDULE -'B'

Item 10

Name of Work :-Improvements and Development of Raj Park In Yelahanka New Town Ward No 04 of Yelahanka
Satellite Town sub Division

SI	Description	Unit	Approved Qty	Rate quoted by the contractor approved rates Sri. G VENKATE GOWDA	
				Rate	Rate in Words
1	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenances required to complete the work.(V-I.No 1.4,Page No-5 of PWD SR 2021-22)	Cum	256.84	214.52	Two Hundred Fourteen Paise FiftyTwo Only
2	Providing and laying in position plain cement concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork shall be paid separately)Mix 1:3:6 (M10) Using 40 mm nominal size graded crushed coarse aggregates (V-1, P.No-15, I No-2.1.3 of PWD SR 2021-22)	Sqm	33.92	6634.07	Six Thousand Six Hundred ThirtyFour Paise Seven Only
3	Providing Size Stone masonry with hard stone in foundation & plinth with Cement mortar 1:6 (1 cement : 6 coarse sand) (V-II, No-5.4, P.No-9 of PWD SR 2021-22)	Cum	184.32	6253.46	Six Thousand Two Hundred FiftyThree Paise FourtySix Only


Executive Engineer,
Yelahanka Division,
B.B.M.P. Bangalore-64.

	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) Mix 1:2:4 (M15) Using 20 mm nominal size graded crushed coarse aggregates	Cum	10.44	7030.82	Seven Thousand Thirty Paise EightyTwo Only
5	Fabricating, providing and erecting in position of MS Hot Dip Galvanised Sq. Hallow Poles of 132 X 132 Heavy gauge of length 3000mm with MS. Hot dip Galvanised grill work as per approved design and drawing of chief architect. Using 12 X 75mm galvanised flat for alround frame and 20 X 20mm galvanised forged design with square for vertical at 150mm c/c as shown in the drawing including providing forged ornamental arrowhead at top and bottom. The work is inclusive of throughing flat, square rods, placing welding all the joints, including grinding, finishing 2 coats of anticorrosive paint over one coat of metal primer. The rate is inclusive of all materials like MS. Hollow galvanized pipe, flats, forged square rods, cost of labour for all items of work cost painting, welding, cutting, grinding with all lead and lift as per specification including loading and unloading with cost and conveyance of all materials, labour, machinery and incidental charges for the successful completion of the work as per the direction of the Engineer-in-charge of the work. (Data Data)	Sqm	421.80	16388.06	Sixteen Thousand Three Hundred EightyEight Paise Six Only
6	Fabricating, providing and erecting in position Hot dip galvanised Gate. Using 72 X 72 X 4.8mm Sq. GI Pipe Frame with Top pipe bending in heavy duty hydraulic press with sand packing and hot bending to form double arch as per drawing profile, 20mm hot dip galvanised sq. rod for verticals at 150mm c/c, as shown in the drawing including providing hot dip galvanised forged ornamental design in between sq. rods and heads at top, middle and bottom. Intermediate supports of 75X12 mm and 50X6 mm arch bend to hot dip galvanised flats. The work is inclusive of throughing GI flat GI sq. rods, placing, welding all the joints including grinding, finishing metal putty, painting two coats enamel painting. The rate is inclusive of all materials like GI sq. pipe, GI sq. rods, GI forged designs etc., heavy duty hinges are made out of 75mm solid sq. block assembled with 20mm dia bearing in three places for each flop. Heavy Duty Locking arrangements at tow places including cost of labour, painting, erecting charges using hoist pulley cranes with all lead and lift, loading, transportation, unloading,	Sqm	25.00	22385.48	TwentyTwo Thousand Three Hundred EightyFive Paise FourtyEight Only

Executive Engineer,
Yelahanka Division,
B.B.M.P, Bangalore-64

	Supplying and fixing M15 grade precast cement concrete Kerb stones for Roadway, Sidewalls and gutters fixed with CM 1:3 fixed and finished in line as per direction of Engineer in charge. (The cost of PCC shall be paid extra) 600 x 300 x 150 mm Kerb Stone (V-III No-6.3, P No-146 of PWD BCSR 2021-22)	m	67.50	487.87	Four Hundred EightySeven Paise EightySeven Only
8	Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces (P.No.56, L.No.8.10 of PW, P&IWTDR SR 2021-22)	Sqm	23.63	98.03	NinetyEight Paise Three Only
9	Providing, laying & fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mix finished with flush pointing using white cement, including cost of materials, mortar, including cutting, gridding the edge to half/full round wherever required, labour, curing complete as per specification. (V-II, P.No.65, L.No.9.40 of PW, P&IWTDR SR 2021-22)	Sqm	40.50	1313.67	One Thousand Three Hundred Thirteen Paise SixtySeven Only
10	Executive Bench- Made out of Sadarahalli grey stone with hand supports with 3 line finishing with arch design with 100mm slabs. Height 90x Length 1500 width 45 cms (Data approved rate)	Each	15.00	19082.70	Nineteen Thousand EightyTwo Paise Seventy Only
11	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m ³) (V-III Page No.3, Item No.1.1 Cof PWD SR 2021-22)	Cum	256.84	85.35	EightyFive Paise ThirtyFive Only
12	Cost of Haulage Excluding Loading and Unloading Taking output 25 t load and lead 10 km = 250 t.km (V-III Page No.3, Item No.1.4C of PWD SR 2021-22) Lead 8 Km	t.Km	328.76	46.13	FourtySix Paise Thirteen Only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,